State of Oklahoma
Office of Management and Enterprise Services
Division of Capital Assets Management
Construction and Properties Department

BID TABULATION SHEET

CAP Project Name: Water Well Replacement

CAP Project Number: 16081

Project Location: Thunderbird State Park - Norman, OK

Bid Date: 11/5/15

Using Agency: Oklahoma Tourism and Recreation Department

Bidder's Name	**MEYER PUMP SERVICE**			
City, State	**NORMAN, OK**			
Notes	BANK CHECK			
Bid Security	Yes	X	No	
Affidavits	Yes	X	No	
Addenda Received	1			
Days	60			
Base Bid "A"	**$83,041.65**			

UNIT PRICES

Description	Est. Qty.	Unit Price	Total
Surface Casing	30	$90.00	$2,700.00
Drill and develop water well	200	$55.00	$11,000.00
7.5 hp, 55 GPM submersible pump, in place	1	$3,826.00	$3,826.00
Pump column, 2" steel sch. 40 with threaded joints	200	$28.72	$5,744.00
Down-stream instrumentation and piping, in place	1	$2,903.65	$2,903.65
Well enclosure foundation, steel pipe fence, and mowing strip	1	$7,500.00	$7,500.00
Well enclosure and heating and ventilation equipment, in place	1	$5,500.00	$5,500.00
Hydro-pneumatic tank installation	5	$900.00	$4,500.00
Well house #2 piping, valves, and meters, in place	1	$18,230.00	$18,230.00
Chemical feed pumps	2	$775.00	$1,550.00
Chemical feed solution tank and equipment, in place	1	$586.00	$586.00
Well house #2 heating and ventilation equipment, in place	1	$3,200.00	$3,200.00
Electrical power and controls, in place	1	$3,500.00	$3,500.00
Electrical power from meter to well house #2	1	$2,800.00	$2,800.00
Plugging of existing well	300	$8.34	$2,502.00
Demolition of existing well house #1	1	$2,500.00	$2,500.00
Removal of all tanks, piping, wiring, controls, and electrical panels at well house #2	1	$500.00	$500.00
Mobilization	1	$4,000.00	$4,000.00
Total Unit Prices:	**$83,041.65**		